

# kontron

The Power of IoT

## FRMCS rendszer jövőképe és a Kontron részvétele a fejlesztési és pilot folyamatokban

---


Sümeg – 2025.10.21.

KONTRON Transportation Confidential



# We are building the bridge from GSM-R to FRMCS

Focus on near future




# Our Mission

## Building the bridge between two worlds



# One Concept, One Strategy, One Portfolio towards FRMCS **kontron**

The Power of IoT



# Kontron's FRMCS credentials



## FRMCS working groups

Contributing to the FRMCS specification process (SuperGroup, FIS WG, ..)



## Europe's Rail JU

Innovation Pillar (R2DATO)  
System Pillar, FRMCS Deployment Subgroup



## ERA EECT Reviews

Finalization of FRMCS V2 specifications



FRANCO-GERMAN ECOSYSTEM  
FOR PRIVATE 5G NETWORKS

## 5GRACOM

Coexistence GSM-R / FRMCS in 900MHz  
Hybrid FRMCS networks Multipath Tech.



## 5G Rail

FRMCSv1 sytem validation with  
focus on TOBA integration & testing

finalized



## 5G Network Hybridization

**Digitale Schiene**  
### Deutschland

MCX technology in FRMCS testing  
Erzgebirge Test Track



## MORANE2

European FRMCSv2  
testing & validation project



## Technical Committee

Railway Communication (TC-RT)  
TS 103 765 -1..5 Transport, Service, OB, TS, UE  
TS 103 792 Interworking Function



## FRMCS / MCX Plugtests

Multi-Vendor Testing & Validation



## Specification Working Groups

Service & System Aspects (SA WG1 + WG6)  
RANx + CNx



## ETCS-FRMCS compatibility

Onboard FRMCS migration challenges  
Baseline 4 vs Baseline light vs Adapter solution

finalized

# Research Projects with (Pre-) FRMCS

## Field trials

- › Shift2Rail – Adaptable Communication System (ACS), Cyber Security (Protection Profile for ACS)
- › 5G Victory – Implementation of Vertical Use case for Railways
- › 5GRail – Development of prototypes for FRMCS
- › Pre-Engineering agreements

Projects ended  
in 2024

- › DB FRMCS/MCx Study and Trial
- › Europe's Rail – Innovation Pillar R2DATO

Field Tests ongoing  
till 2026

- › 5G-RACOM – Whitespace and multipath pilot in hybrid network
- › SNCF 5G Hybridisation

Field Tests in  
2025


- › MORANE 2

Just started !  
Field Tests 2027



KONTRON Transportation is leading or being one of the main supplier actors in those projects related to communication


# The European Timeline



# Ongoing research projects - 5G-RACOM







## 5G for Resilient and Green RAIL COMMunications

- › German-French Research Project aims at investigating, developing and demonstrating key technologies to achieve a green, resilient, and future-proof FRMCS system – led by SNCF and DB
  - › French part: “exploiting the available RMR frequency spectrum most efficiently “
    - >**co-located approach and Whitespace Pilot**
  - German part: “extending FRMCS towards additional public frequency spectrum via a hybrid network architecture “ -
    - >**Multi-path functionality in Hybrid network** (own 5G plus public MNO 5G network)



Planned Duration: 3 years - 1.12.2022-30.11.2025

# 5G-RACOM – Multipath Use Cases

| UC1                                                                                            | UC2                                                                                                                         | UC3                                                                                                                | UC4                                                                                                                  | UC5                                                                                                                                                 | UC6                                                                                                   |
|------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------|
| Application-Specific Path Selection                                                            | Fallback                                                                                                                    | Resilience via Path Selection                                                                                      | Resilience via Replication                                                                                           | Coverage Extension                                                                                                                                  | Capacity Extension                                                                                    |
|               |                                            |                                  |                                   |                                                                  |                    |
| The PMNO network is by default used for applications that may not use FRMCS (e.g. Diagnostics) | In case the FRMCS network becomes unavailable due to failures or unintended coverage holes, the PMNO network is taking over | In case the FRMCS network quality is poor (QoS is not fulfilled), some data flows are switched to the PMNO network | In case the FRMCS network quality is poor (QoS is not fulfilled), some data flows are duplicated to the PMNO network | In case the FRMCS network coverage ends (intentionally) because the track is not (yet) equipped with FRMCS, the PMNO network takes temporarily over | In case the capacity (data rate) of the FRMCS network is not sufficient, the PMNO network complements |

# Ongoing research projects - 5G-RACOM

## WP2 - Coexistence of FRMCS & GSM-R


### Whitespace Approach



#### › Whitespace

- › Standard 3GPP REL17 and above.
- › Leverage existing ecosystem 5MHz (5G SA UE)
- › Maximize spectrum usage
- › No impact on GSM-R
- › Allows smooth migration from GSM-R to FRMCS in a single step.
- › Ready technology after 5G RACOM

### Co-located Approach




#### › Below 5MHz (3MHz)

- › Requires on going 3GPP standardization R18/19,
- › Impact on 5G UE/Chipset (small ecosystem)
- › Require GSM-R reparenting (4 to 2,6 MHz)
- › Migration from GSM-R to FRMCS in several steps
- › Requires re-engineering to 5MHz when GSM-R OFF
- › No product and niche ecosystem

# MORANE2 facts and engagement

- › Duration: **30 months**
- › Overall Project Funding: 23 Mio€
- › Project Objectives
  - › **Validation of FRMCS V2 Specification** in lab and field on several tracks
  - › Deliver **inputs for FRMCS Specification V3** based on the results of the project
- › **UIC as Project Coordinator**
  - › 4 active Railways (providing tracks for field tests)
  - › 6-7 passive Railways (observing the activities)
  - › 12 FRMCS Suppliers
  - › 1-2 Public MNOs
  - › 2 ETCS/ATO Supplier



| Start     | Title                                          | Lead     | 4Q 2024 | 1Q 2025 | 2Q 2025 | 3Q 2025 | 4Q 2025 | 1Q 2026 | 2Q 2026 | 3Q 2026                                        | 4Q 2026 | 1Q 2027 | 2Q 2027      | 3Q 2027 |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
|-----------|------------------------------------------------|----------|---------|---------|---------|---------|---------|---------|---------|------------------------------------------------|---------|---------|--------------|---------|----|----|----|----|------|----|-----|------|------|------|------|----|------|----|-------|--------|------|------|----|------|------|----|--|--|
|           |                                                |          | 1       | 2       | 3       | 4       | 5       | 6       | 7       | 8                                              | 9       | 10      | 11           | 12      | 13 | 14 | 15 | 16 | 17   | 18 | 19  | 20   | 21   | 22   | 23   | 24 | 25   | 26 | 27    | 28     | 29   | 30   | 31 | 32   | 33   | 34 |  |  |
| WP 1      | Test Design and Planning                       | UIC      |         |         |         |         |         |         |         | Test Design and Planning                       |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 1.1  | FRMCS Test Specifications                      | UIC      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    | D1.1 |    |     |      | D1.3 |      |      |    |      |    |       |        |      |      |    | D1.5 |      |    |  |  |
| Task 1.2  | Test Plan and Test Methodology for Lab         | UIC      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     | D1.2 |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 1.3  | Test Plan and Test Methodology for Field       | UIC      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      | D1.4 |    |      |    |       |        |      |      |    |      |      |    |  |  |
| WP 2      | System Component Preparation and Architectures | UNIFE    |         |         |         |         |         |         |         | System Component Preparation and Architectures |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.1  | Telecom (FRMCS Transport and Service Layer)    | KONTRON  |         |         |         |         |         |         |         |                                                |         |         | Telecom      |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.2  | TOBA & TS GW                                   | ATSA     |         |         |         |         |         |         |         |                                                |         |         | Toba & TS GW |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.3  | Cab radio                                      | SMO      |         |         |         |         |         |         |         |                                                |         |         | Cab radio    |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.4  | Dispatcher                                     | ROT      |         |         |         |         |         |         |         |                                                |         |         | Dispatcher   |         |    |    |    |    |      |    |     |      | D2.2 |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.5  | Monitoring & Measurement Metrics               | VIAVI    |         |         |         |         |         |         |         | Monitoring & Measurement Metrics               |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.6  | Data applications (ETCS/ATO/TCMS Simulators)   | CAF      |         |         |         |         |         |         |         | Data applications (ETCS/ATO/TCMS)              |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.7  | Radio Modules                                  | FUNKWERK |         |         |         |         |         |         |         |                                                |         |         | Radio Module |         |    |    |    |    | PC3  |    | PC1 |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.8  | FRMCS/GSM-R Interworking                       | NOKIA    |         |         |         |         |         |         |         | FRMCS/GSM-R Interworking                       |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 2.9  | Test Architectures                             | INFRAGO  |         |         |         |         |         |         |         | Test Architectures                             |         |         |              |         |    |    |    |    |      |    |     |      | D2.1 |      |      |    | D2.3 |    |       |        |      |      |    |      | D2.4 |    |  |  |
| WP 3      | Lab Test Preparations and Execution            | ERI      |         |         |         |         |         |         |         | Lab Test Preparations and Execution            |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.1  | Staging of Lab Environment Ericsson            | ERICSSON |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.2  | Staging of Lab Environment Nokia               | NOKIA    |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      | D3.1 |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.3  | Staging of Lab Environment Kontron             | KONTRON  |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.4  | Lab Tests Ericsson                             | ERICSSON |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.5  | Lab Tests Nokia                                | NOKIA    |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.6  | Lab Tests Kontron                              | KONTRON  |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 3.7  | Evaluation & Return on Experience              | UIC      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| WP 4      | Field Test Preparations and Execution          | TRV      |         |         |         |         |         |         |         | Field Test Preparations and Execution          |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.1  | Staging of Test Environment Spain              | ADIF     |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.2  | Field Tests Spain                              | ADIF     |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    | Spain |        | D4.1 |      |    |      |      |    |  |  |
| Task 4.3  | Staging of Test Environment Sweden             | TRV      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.4  | Field Tests Sweden                             | TRV      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       | Sweden |      | D4.2 |    |      |      |    |  |  |
| Task 4.5  | Staging of Test Environment Germany            | INFRAGO  |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.6  | Field Tests Germany                            | INFRAGO  |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.7  | Staging of Test Environment Spain HS           | ADIF     |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.8  | Field Tests Spain HS                           | ADIF     |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.9  | Staging of Test Environment Netherlands        | PRORAIL  |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.10 | Field Tests Netherlands                        | PRORAIL  |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| Task 4.11 | Evaluation & Return on Experience              | UIC      |         |         |         |         |         |         |         |                                                |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| WP 5      | Dissemination                                  | UNIFE    |         |         |         |         |         |         |         | Dissemination                                  |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |
| WP 6      | Project Management                             | UIC      |         |         |         |         |         |         |         | Project Management                             |         |         |              |         |    |    |    |    |      |    |     |      |      |      |      |    |      |    |       |        |      |      |    |      |      |    |  |  |

# MORANE2 KONTRON Field Tests Involvement

## › Spain – ADIF

- › Conventional line: 5G-Core, 5G RAN (900 MHz and 1900 MHz), MCX/IMS
- › Highspeed line: 5G-Core, 5G RAN (1900 MHz), MCX/IMS

## › Germany – DB:

- › MCX/IMS, Trackside Gateway, dispatcher




## › Netherlands – ProRail:

- › MCX/IMS

## › Sweden – Trafikverket

- › MCX/IMS, dispatcher

- › Kontron is active on all tracks and took the biggest portion of the overall invest/budget delivering 5G-Core, 5G RAN (900 and 1900 MHz), MCX/IMS, trackside gateway and dispatcher core for the field tests



# MORANE2 Field Network Setup

|             | DB                    | ADIF conv.        | ADIF HS            | Trafikverket      | Prorail                       |
|-------------|-----------------------|-------------------|--------------------|-------------------|-------------------------------|
| RAN 900Mhz  |                       | Kontron           |                    |                   |                               |
| RAN 1900Mhz | E// - Nokia           | Kontron           | E// - Kontron      | E//               | E// - MNO KPN                 |
| 5GC         | E// - Nokia           | Kontron           | E//                | E//               | E//                           |
| MCX / IMS   | Kontron –Nokia/Eviden | Kontron           | Kontron            | Kontron           | Kontron                       |
|             |                       |                   |                    |                   |                               |
| CabRadio    | Funkwerk              | Funkwerk          | Funkwerk           | Siemens           | Funkwerk                      |
| OBGW        | Funkwerk<br>Siemens   | Alstom<br>Hitachi | Funkwerk<br>Alstom | Alstom<br>Siemens | Alstom<br>Funkwerk<br>Siemens |
| TSGW        | Kontron               | Hitachi           | Alstom             | Alstom            | Alstom                        |
| Dispatcher  | Kontron<br>Frequentis | Teltronic         | Eviden             | Kontron           | ROT                           |

# MORANE2 – Kontron's Involvement & Contribution

## KONTRON

DISP

TRGW

MCX

IMS

5GC

RAN

OBGW

CAB



DISP

TRGW

MCX

IMS

5GC

RAN

OBGW

CAB



DISP

TRGW

MCX

IMS

5GC

RAN

OBGW

CAB



DISP

TRGW

MCX

IMS

5GC

RAN

OBGW

CAB



DISP

TRGW

MCX

IMS

5GC

RAN

OBGW


CAB



Thanks to its experience and portfolio, Kontron is active on all tracks!

# KT FRMCS n100 & n101 Modem

Enabling Radio RMR




## White Space 900 Mhz

1. 1<sup>st</sup> tests Racom made on Transposed modem
2. Then 'Real' Modem n100 required!




## MORANE 2

1. RAN KT n100 & n101 on ADIF – 2 lines
2. CAB Funkwerk, OBGW, RAN E// & Nokia



Kontron has engaged the main 5G chipset supplier to work on a plan to embed railway functions and feature in a commercial chipset and develop modules and modems for the emerging FRMCS market.



Availability of FRMCS compliant 5G modems supporting RMR spectrum (n100/n101)

# kontron

---

Copyright © 2025 Kontron Transportation GmbH. All rights reserved. All data is for information purposes only and not guaranteed for legal purposes. Information has been carefully checked and is believed to be accurate; however, no responsibility is assumed for inaccuracies. Kontron and the Kontron logo and all other trademarks or registered trademarks are the property of their respective owners and are recognized. Specifications are subject to change without notice.